

Effects of water scarcity awareness and climate change belief on recycled water usage willingness: Evidence from New Mexico, United States

Minh-Hoang Nguyen^{1,2*}, Duc Manh Doan³, Hanh Kim Dong⁴, Van Thi Nguyen⁴, Hanh Hong Dao⁵, Duy Duc Trinh⁵,
 Nhait Thi Nguyen⁶, Kim Nguyet Kieu⁷, Nhung Quynh Thi Le⁷, Ha Thu Thi Hoang⁷, Van Ngoc Thi Dam⁷,
 Dung Hoang Do⁸, Thu Thi Vu⁸, Tu That Ton⁹, Nhi Yen Nguyen³, Nhi Van Nguyen³, Thu Tai Le⁷, Hoa Tuan Pham⁷,
 Binh Thi Khuat⁷, Tung Thanh Nguyen⁷, Anh Viet Thuy Nguyen¹⁰, Vu Thien Tran¹¹, Son Kim Thi Nguyen⁶,
 Tra Thanh Nguyen⁷, Hang Thanh Pham⁶, Linh Ha Nguyen⁶, Hien Thanh Thi Vu⁶, Linh Thu Hoang⁶,
 Dung Kim Nguyen⁶, Chi Yen Nguyen⁶, Chi Linh Nguyen¹², Minh Duc Vu¹³, Lan Phuong Thi Le⁴, Van-Cuong Do^{14*}

¹Centre for Interdisciplinary Social Research, Phenikaa University, Yen Nghia Ward, Ha Dong District, Hanoi, Vietnam

²A.I. for Social Data Lab (AISDL), Vuong & Associates, Yen Nghia Ward, Ha Dong District, Hanoi, Vietnam

³Foreign Trade University, 91 Chua Lang Street, Lang Thuong Ward, Dong Da District, Hanoi, Vietnam

⁴Thuy Loi University, 175 Tay Son Street, Trung Liet Ward, Dong Da District, Hanoi, Vietnam

⁵Thuongmai University, 79 Ho Tung Mau Street, Mai Dich Ward, Cau Giay District, Hanoi, Vietnam

⁶Hanoi University, Km 9, Nguyen Trai Street, Trung Van Ward, Nam Tu Liem District, Hanoi, Vietnam

⁷Banking Academy of Vietnam, 12 Chua Boc Street, Quang Trung Ward, Dong Da District, Hanoi, Vietnam

⁸VNU University of Education, 144 Xuan Thuy Street, Dich Vong Hau Ward, Cau Giay District, Hanoi, Vietnam

⁹University of Science and Education, The University of Da Nang, 459 Ton Duc Thang Street, Hoa Khanh Nam Ward, Lien Chieu District, Da Nang City, Vietnam

¹⁰School Quang Tri International Integration School, Lai Phuoc Urban Area, Dong Luong Ward, Dong Ha City, Quang Tri Province, Vietnam

¹¹Vietnam - Korea University of Information and Communication Technology, 470 Tran Dai Nghia Street, Hoa Quy Ward, Ngu Hanh Son District, Da Nang City, Vietnam

¹²Thanh Do University, Km 15, Highway 32, Kim Chung Town, Hoai Duc District, Hanoi, Vietnam

¹³VNU University of Science, 334 Nguyen Trai Street, Thanh Xuan Trung Ward, Thanh Xuan District, Hanoi, Vietnam

¹⁴Hanoi University of Science and Technology, 1 Dai Co Viet Street, Bach Khoa Ward, Hai Ba Trung District, Hanoi, Vietnam

Received 6 November 2023; revised 3 January 2024; accepted 21 February 2024

Abstract:

The global water crisis is being exacerbated by climate change, even in the United States. Recycled water is a feasible alternative to alleviate the water shortage, but it is constrained by humans' perceptions. The current study examines how residents' water scarcity awareness and climate change belief influence their willingness to use recycled water directly and indirectly. Bayesian Mindsponge Framework (BMF) analytics was employed on a dataset of 1831 residents in Albuquerque, New Mexico, an arid inland region in the US. We discovered that residents' willingness to use direct recycled potable water is positively affected by their awareness of water scarcity, but the effect is conditional on their belief in the impacts of climate change on the water cycle. Meanwhile, the willingness to use indirect recycled potable water is influenced by water scarcity awareness, and the belief in climate change further enhances this effect. These findings implicate that fighting climate change denialism and informing the public of the water scarcity situation in the region can contribute to the effectiveness and sustainability of long-term water conservation and climate change alleviation efforts.

Keywords: arid region, drinking, eco-surplus culture, Mindsponge Theory, potable water, sustainable development, water shortage.

Classification numbers: 4.1, 7

1. Introduction

Water, in general, and potable water, in particular, is indispensable for human beings. Water demand has rapidly increased due to industrialization, urbanization, population growth, and economic development. Due to the excessive water usage, water resources have

depleted swiftly. Water scarcity, generally referred to as the condition in which the demand for water by all sectors exceeds the water supply, has become an alarming global issue, drawing much political and public concern.

According to a report published by UNESCO on behalf of UN-Water [1], it is estimated that about 2 billion

*Corresponding authors: Email: hoang.nguyenminh@phenikaa-uni.edu.vn, cuong.dovan@hust.edu.vn

individuals, accounting for 26% of the global population, lack access to clean drinking water. Additionally, the report highlights that around 3.6 billion people, constituting 46% of the population, do not have access to adequately managed sanitation facilities. Some projections suggest that the number of worldwide urban residents experiencing water scarcity is anticipated to increase twofold, rising from 930 million in 2016 to a range of 1.7 to 2.4 billion by 2050. The increasing prevalence of severe and prolonged droughts also exerts pressure on ecosystems, resulting in grave ramifications for various plant and animal species [1]. As a result, the solution for water scarcity and quality is set as the main focus in multiple international, regional, and national organizations, associations, committees, and conferences [2, 3].

Global climate change significantly contributes to the current water scarcity crisis. It is a worldwide issue that impacts the access and quality of water resources, especially potable water sources [4, 5]. Climate change affects the world's water in complex ways. Infectious disease epidemics frequently coincide with extreme weather events, as microorganisms, vectors, and reservoir animal hosts take advantage of the altered social and environmental conditions resulting from such occurrences [6]. Rising temperatures can also lead to the rise in seawater levels and the intrusion of salt water into the coastal aquifers, besides facilitating the rise of deadly pathogens in freshwater sources, making the water dangerous for people to drink [7]. Climate change can exacerbate water stress in areas with minimal water resources, leading to increased competition for water and even conflicts [8]. In a recent study, X. Fan, et al. (2023) [9] suggest climate change can also affect pipe failures in the United States (US).

The water stress in the Southwest of the US has intensified in recent years due to more frequent droughts, more variable rainfall, and less reliable water supplies induced by climate change [10, 11]. A recent analysis by researchers from the World Resources Institute shows that the Colorado River Basin is one of the world's most water-stressed regions, with the water stress level similar to arid countries like Saudi Arabia and Qatar. Among seven States in the Colorado River Basin, Arizona is the most severely water-stressed State, while New Mexico, where the study site is located, is ranked second [12]. It is estimated that the Colorado River's flow has declined by around 10.3% because of anthropogenic increases in both temperature and CO₂ since 1880 [13]. In 2022, more than 90% of the New Mexico region suffered from the severe

drought caused by the greatest wildfire in state history and some of the driest months ever recorded [14, 15].

With the looming challenges of water scarcity worldwide, unconventional water resources are considered viable alternatives to freshwater, especially in arid and semi-arid areas [16]. These water resources require new technologies and specialized processes to convert them into safe and usable states to complement human life [17, 18]. Z. Karimidastenaie, et al. (2022) [16] have identified twelve general types of these unconventional resources, with desalination of saltwater and treatment of wastewater being the most prominent methods. The improvement of technology, analytical methods, and microbiology has allowed wastewater to be recyclable for irrigation practices and indoor applications such as toilet flushing [19, 20]. In certain countries and regions, recycled water quality has reached the drinking water standard [21]. As such, various countries around the globe have implemented multiple initiatives to encourage the use of recycled wastewater to alleviate the burden on freshwater [19].

Yet, public perceptions and acceptance of recycled wastewater are identified as one of the most significant barriers against its usage rather than the technology itself [19]. In studying the public response to the usage of reclaimed water, K.J. Ormerod, et al. (2013) [20] found that trust in water authorities can significantly impact public attitudes towards recycled water. In exploring the role of emotions in water reuse behavior, Y. Gao, et al. (2019) [21] found that the perceptions of recycled water can initiate positive and negative feelings, significantly affecting the initiation, formation, and sustainability of recycled water behavior.

A thorough review by K.S. Fielding, et al. (2018) [22] identified socio-demographic characteristics, psychological elements, and water characteristics as three major predictors of public acceptance. While most studies found mixed results about how different socio-demographic groups embrace recycled water, studies focused on mental processes found homogenous trends. Specifically, high health risk perceptions led to low acceptance of recycled water. Trust in authorities also appeared as a critical factor. Trust in authorities might help alleviate the risk perceptions, which could influence acceptance of proposed water management schemes.

Several studies investigate the link between perceived water scarcity and recycled water acceptance, but the results seem inconsistent. C. Hou, et al. (2021) [23]

discovered that the disclosure of information regarding regional water shortages and the promotion of public awareness regarding the protection of water environments are positively associated with the willingness to use recycled water. Additionally, disclosing regional water shortage information indirectly influences public acceptance of recycled water by shaping their awareness of water environment protection. Meanwhile, two studies found no significant relationship [22, 24, 25]. The discrepant findings hint at other factors moderating the relationship between water scarcity awareness and recycled water acceptance. Moreover, while general environmental concerns are found to be related to greater acceptance of recycled water, few studies have investigated the effects of climate change beliefs on recycled water acceptance.

Due to water scarcity in the city of Albuquerque, New Mexico, the Albuquerque-Bernalillo County Water Utility Authority (ABCWUA), the sole provider of water and wastewater services to the city, has considered direct and indirect potable water reuse in its 100-year water plan [26]. However, studies examining factors supporting the implementation of direct and indirect potable water reuse remain limited. Some analyses were performed [27-29], but they did not explore the potential effect of water scarcity awareness and the moderation effect of climate change belief on residents' willingness to use recycled water. Insights from the current study can benefit ABCWUA, water planners, and policymakers in the region to improve the effectiveness of recycled water usage programs.

Therefore, our study aims to fill in these gaps by performing BMF analytics on a dataset of 1831 residents in Albuquerque, New Mexico, USA, for the following objectives:

- Examine the effect of residents' water scarcity awareness on their willingness to use direct and indirect recycled water.
- Examine the moderation effect of the belief in climate change on the relationship between the residents' water scarcity awareness and their willingness to use direct and indirect recycled water.

The study consists of five main sections. The first section introduces the study's importance, rationale, and objectives. The second section elaborates on the theoretical foundation of the model construction (i.e., Mindsponge Theory) and the materials and methods employed. The third section presents the estimated

results using the Bayesian analysis, while the final section discusses the implications of the study's findings.

2. Methodology

2.1. Theoretical foundation

The Mindsponge Theory was utilized as the theoretical foundation for constructing models in this study. The theory was initially the mindsponge mechanism developed by Q.H. Vuong, et al. (2015) [30] to explain how top managers absorb new values and eject waning ones out of their mindset. The term "mindsponge" is coined by analogizing the mind to a sponge, which expels unsuitable values and absorbs new ones compatible with its core values [30]. Capitalizing on the new evidence discovered in life, neuro-, and ecological sciences, the mechanism was further developed into Mindsponge Theory to explain better a wider range of processing systems and socio-psychosocial phenomena [31].

The Mindsponge Theory offers a dynamic perspective on information processing that can help connect the socio-psychological phenomena with the fundamental level of human cognition (e.g., neurons), address intricate aspects of human thinking, and elaborate and enhance existing psychological and social theories and frameworks.

Theory of Planned Behavior (TPB) is a well-known psychological theory that explains how humans' beliefs are linked to behaviors [32, 33], so it has been employed to study behaviors related to conservation, including water conservation [34-37]. Specifically, TPB was recently used to explore the effects of attitudes, subjective norms, perceived behavioral control, and connectedness to water on behavioral intent related to landscape irrigation among Florida, Georgia, and Alabama residents. K.E. Gibson, et al. (2023) [38] found that subjective norms, perceived behavioral control, and connectedness to water were positive predictors of behavioral intent and actual behaviors related to water conservation. Although TPB is an effective theory to explain the connection between beliefs, intentions, and behaviors, it lacks the ability to deal with the dynamics of human thinking that we aimed to study in this study: the non-linear relationship between awareness of water scarcity and recycled water usage willingness (moderated by the climate change belief). Thus, the Mindsponge Theory, with its capability to explain the continuous dynamic information absorption-process-ejection mechanisms of the mind, is expected to complement the TPB in reasoning the cognition and behavior-shifting processes.

Mindsponge Theory includes two primary spectrums [31]: The mind, an information collection and processing unit, and the broader environment, encompassing systems like the Earth system, social systems, and the mind. The mind's primary objective is to ensure its system's prolongation in one way or another, including survival, growth, and reproduction. Conceptually, the mind comprises three major components: the mindset, buffer zone (comfort zone), and multi-filtering system. The mindset is defined as a set of highly trusted information (or core values), while the buffer zone temporarily holds information for the multi-filtering process.

The multi-filtering system serves two key functions. When information enters the mind due to the absorption through the sensory systems, it undergoes two processes. Information consistent with the core values is integrated. However, suppose new information significantly deviates from core values. In that case, it goes through a differentiation process, evaluating the cost and benefit of the information for subsequent acceptance, rejection, or storage for later evaluation. Generally, if new information is seen as potentially beneficial, it is accepted into the mindset, influencing subsequent thinking and behaviors. If it is perceived as costly, it is likely rejected. Information with ambiguous values is stored in the buffer zone for later assessment when sufficient information is available [39].

From the mindsponge information-processing perspective, the residents' awareness of water scarcity issues can be deemed equivalent to information related to water scarcity issues stored within the mind. With a larger amount of such information in the mind, subsequent information processes, thinking, and behaviors are more likely to be affected. In other words, when residents perceive the water scarcity issues in the region, they are more likely to accept solution-related information into the mindset to minimize the risk of water shortage, that is, using water recycled water directly and indirectly. Therefore, we assume that higher awareness of water scarcity is positively associated with the willingness to recycled water usage.

However, core values (beliefs) can also affect the information process. Awareness of water scarcity does not necessarily make people think the water shortage is a persisting problem, but it depends on the situation. If people believe in climate change's impacts on the water cycle, they might consider water scarcity a persisting

problem. Otherwise, the water scarcity might be perceived as temporary and to recover in the future. As a result, we also assumed that the climate change belief moderates the relationship between awareness of water scarcity and recycled water usage willingness.

These assumptions will be tested through models constructed in the following subsection.

2.2. Model construction

2.2.1. Variable selection and rationale

Data used in the current study resulted from a large-scale public survey delivered via mail to a random sample of 4000 water-utility account holders in Albuquerque, New Mexico, USA. The survey collection was conducted by L.N. Distler, et. al. (2020c) [40] in collaboration with the Albuquerque Bernalillo County Water Utility Authority (ABCWUA) (2016) [26], the sole supplier of water and wastewater services to the broader Albuquerque metropolitan region with over 600,000 water users. The dataset and its description have been peer-reviewed and published in Data in Brief [40]. The dataset was also employed in other studies about water consumption behaviors in Albuquerque, New Mexico [27-29].

The survey queried ABCWUA account holders about their water knowledge, water consumption habits, attitudes toward water-related issues, and demographic data. The survey was available in four versions, with the only difference being on page five: Version 1 was the control and had no additional content, whereas the other three versions each had a different collection of educational materials on page five since specific sorts of educational materials are thought to alter perceptions and views relating to water reuse. Versions 2, 3, and 4 supply information on "Water sources and reliable supplies", "Environmental benefits of water reuse", and "The urban water cycle", as defined in the codebook and survey instrument, respectively.

Eight focus groups and 12 debriefing sessions were conducted with individual members of the studied population to design the survey. The focus groups took place in July, October, and November of 2016, while the debriefing sessions took place in August, October, and November of the same year. Eight 90-minute focus groups with 7-10 individuals each help test prototype survey questions to improve the survey content. Participants had to be at least 18 years old and ABCWUA clients to be included. L.N. Distler, et al. (2020c) [40] tested the

draft survey on 12 individual members of the sample population in a series of one-on-one survey debriefing sessions halfway through and following the completion of the focus groups. Debriefings helped researchers to check that survey questions and materials were accurately evaluated and comprehended, as well as assess how long it would take to finish the survey.

A random sample of 4,000 accounts was drawn from a database of over 180,000 residential accounts maintained by ABCWUA. Customer names were removed from the sample to safeguard respondent's privacy, and addresses were deleted once data analysis was completed. Each potential survey participant was assigned a unique random code for anonymous tracking of responses. The sample proportions in each quadrant were compared to those in the customer accounts log to confirm that the sample and population proportions matched (within 1%). The survey was collected through mail and Survey Monkey (online).

The database also supplied information regarding the city quadrant where each customer resided. The sample's quadrant proportions were ensured to closely match those in the overall customer accounts database (within a 1% margin). The survey was administered by mail due to the availability of physical addresses, although respondents were offered the option to complete it online using Survey Monkey through a mailed invitation. As the survey was self-reported, we acknowledged some

potential perceptual biases. Furthermore, due to its limitation to the city of Albuquerque, the sample size could not adequately represent regions of the United States that possess distinct geographical and climatic attributes.

A preliminary test was conducted on 200 water utility customers randomly selected to validate the survey instrument. The pretest had two purposes: it estimated the expected response rate for the main survey, and it evaluated the efficacy of the survey administration techniques. Based on the pretest's results, the survey instrument and administration process were refined and sent to a random sample of 4,000 ABCWUA account holders. Eventually, 1831 responses were obtained, with a response rate of 46%.

Four variables retrieved from the dataset were used in this study to build the model: two outcome variables and two predictor variables. Two outcome variables are *DPR_WILL_3* and *IPR_WILL_3*. These two variables represent the respondents' willingness to use recycled water directly and indirectly. *SCARCITY_AWARE* and *CLIMATE* are two predictor variables. While *SCARCITY_AWARE* reflects the respondents' awareness level of water scarcity, *CLIMATE* reflects whether the respondent believes in climate change. Detailed descriptions of these variables are shown in Table 1.

Table 1. Description of variables.

Variables	Description	Type of variable	Value	Details
<i>DPR_WILL_3</i>	Willingness to accept direct potable reuse	Binary*	0 = Unwilling 1 = Willing	Unwilling=506 (27.64%) Willing=856 (46.75%)
<i>IPR_WILL_3</i>	Willingness to accept indirect potable reuse	Binary*	0 = Unwilling 1 = Willing	Unwilling=321 (17.53%) Willing=988 (53.96%)
<i>SCARCITY_AWARE</i>	Awareness of water scarcity issues	Numerical	1 = Not at all aware 2 = Slightly aware 3 = Moderately aware 4 = Very aware 5 = Extremely aware	Mean=3.24 Standard deviation=1.02
<i>CLIMATE</i>	Belief in the impact of climate change on the water cycle in the next 10-40 years	Binary	0 = No 1 = Yes	No = 265 (14.47%) Yes = 1298 (70.89%)

*: Respondents expressing neutral responses to direct or indirect potable reuse are coded as 'Not Applicable' and removed from the analysis.

2.2.2. Statistical model

The first model was constructed to examine the effects of *SCARCITY_AWARE* on *DPR_WILL_3* and the moderation effect of *CLIMATE*:

$$DPR_WILL_3 \sim \text{normal}\left(\log\left(\frac{\mu_i}{1-\mu_i}\right), \sigma\right)$$

$$\log\left(\frac{\mu_i}{1-\mu_i}\right) = \beta_0 + \beta_1 * SCARCITY_AWARE_i + \beta_2 * SCARCITY_AWARE_i * CLIMATE_i$$

$$\beta \sim \text{normal}(M, S)$$

The probability around the mean $\log\left(\frac{\mu_i}{1-\mu_i}\right)$ is determined by the shape of the normal distribution, where the width of the distribution is specified by the standard deviation σ . μ_i indicates the probability that the residential account holder i willing to accept drinking recycled water directly. *SCARCITY_AWARE_i* indicates the awareness level of the residential account holder i about water scarcity issues. *CLIMATE_i* indicates whether the residential account holder i believes in the impact of climate change on the water cycle. Model 1 has four parameters: the coefficients, β_1 and β_2 , the intercept, β_0 , and the standard deviation of the “noise,” σ . The coefficients of the variables are distributed as a normal distribution around the mean denoted M , with the standard deviation denoted S . The logical network for Model 1 is presented in Fig. 1.




Fig. 1. Model 1's logical network.

The second model was constructed similarly to Model 1 but with the outcome variable replaced as *IPR_WILL_3*.

$$IPR_WILL_3 \sim \text{normal}\left(\log\left(\frac{\mu_i}{1-\mu_i}\right), \sigma\right)$$

$$\log\left(\frac{\mu_i}{1-\mu_i}\right) = \beta_0 + \beta_1 * SCARCITY_AWARE_i + \beta_2 * SCARCITY_AWARE_i * CLIMATE_i$$

$$\beta \sim \text{normal}(M, S)$$

IPR_WILL_3 indicates the probability that the residential account holder willing to accept drinking recycled water indirectly. Model 2's logical network is similar to that of Model 1, shown in Fig. 1.

2.3. Analysis and validation

The BMF analytics is a method combining the strengths of Mindsponge Theory and Bayesian analysis for analyzing data in cognitive, psychological, and social research [39, 41]. It is particularly useful in studying psychological processes and mechanisms in several fields, including but not limited to mental health, psychological adaptation, and environmental psychology [42-50],

BMF was applied in this research for several reasons. First, the method combines the reasoning strengths of Mindsponge Theory with the inferential advantages of Bayesian analysis [41]. Second, Bayesian inference evaluates all attributes probabilistically, allowing reliable predictions with parsimonious models that help improve predictability [51-53]. Third, Bayesian inference enables users to use credible intervals for result interpretation instead of the dichotomous decision using p -value, which is suggested to be one of the leading causes behind the reproducibility crisis [54, 55].

There are two main components in BMF analytics: Mindsponge-based model construction and Bayesian analysis. The former component is presented in subsection 2.1, while the second component is explained here. Bayesian analysis comprises five main steps [39]:

- 1) Model construction.
- 2) Prior selection.
- 3) Model fitting.
- 4) Result diagnosis and interpretation.
- 5) Model comparison.

In the current study, we aim to test the model constructed based on Mindsponge-Theory-induced assumptions, so step 5 was not implemented. The models built based on Mindsponge Theory are presented in subsection 2.2.2. As the nature of this study is exploratory, models were constructed with uninformative priors or a flat prior distribution to provide as little prior information as possible for model estimations.

After fitting the constructed models, we employed the Pareto-smoothed importance sampling leave-one-out (PSIS-LOO) diagnostics to check the model's goodness of fit. LOO is computed as follows [56, 57]:

$$LOO = -2LPPD_{LOO} = -2 \sum_{i=1}^n \log \int p(y_i|\theta) p_{post(-i)}(\theta) d\theta$$

The posterior distribution, denoted as $p_{post(-i)}(\theta)$, is calculated based on the data minus data point i . In the R loo package, the PSIS method was used to compute leave-one-out cross-validation k -Pareto values. Commonly, the model is regarded as being fit when a model's k values are below 0.5.

Then, we verified the convergence of Markov chains statistically using the effective sample size (n_{eff}) and the Gelman-Rubin shrink factor ($Rhat$) and visually by trace plots. The Markov chain central limit theorem holds if the Markov chains converge, and the estimated results become reliable and qualified for interpretation. The n_{eff} value represents the number of iterative samples that are not autocorrelated during stochastic simulation. If n_{eff} is bigger than 1000, it is generally considered that the Markov chains are convergent, and the effective samples are sufficient for reliable inference [58]. The $Rhat$ value is alternatively referred to as the potential scale reduction factor or the Gelman-Rubin shrink factor [59]. It should not exceed 1.1 for convergence to be achieved. Commonly, the model is considered convergent if $Rhat=1$.

We employed the bayesvl and the ggplot2 R packages to conduct Bayesian analysis and produce appealing visualizations [60]. The whole code and dataset employed for this research have been deposited in the

Open Science Framework to ensure openness, facilitate future replication, and contribute to lowering scientific costs [61].

3. Results

3.1. Model 1

Model fitting was performed on R version 4.2.1 ("Vigorous calisthenics") using four Markov chains, each consisting of 5000 iterations, with 2000 used for the warmup period. The simulation took 201 s to be completed. The simulated results are displayed in Table 2. First, we checked the goodness of fit between the constructed model and the dataset using the PSIS-LOO test. The test's estimated k -values are shown in Fig. A1, which shows that most of the k -values are below 0.05. These k -estimates suggest that the model fits the data reasonably well.

Table 2. Model 1's estimated results.

Parameters	Mean	Standard deviation	n_{eff}	$Rhat$
<i>Constant</i>	0.47	0.24	4085	1
<i>SCARCITY_AWARE</i>	0.03	0.08	3638	1
<i>SCARCITY_AWARE*CLIMATE</i>	0.09	0.05	4920	1

Source: Generated by authors using the bayesvl R package.

Then, we proceeded with diagnosing the Markov chain convergence. All the coefficients' n_{eff} values are greater than 1000, and the $Rhat$ values are equal to 1, implying that the model's Markov chains have converged well.

We also visualized the trace plots to confirm the Markov chain's convergence (or the Markov chain central limit theorem). Fig. 2 illustrates the coefficients' Markov chains are well mixed around an equilibrium, which is a good signal of convergence.

The simulated results manifest the positive association between *SCARCITY_AWARE*CLIMATE* and *DPR_WILL_3* ($M_{SCARCITY_AWARE}=0.09$ and $S_{SCARCITY_AWARE}=0.05$). The association is reliable as its posterior distribution




Fig. 2. Model 1's trace plots. Source: Generated by authors using the bayesvl R package.




Fig. 3. Model 1's posterior distributions. Source: Generated by authors using the bayesvl R package.

is located entirely on the positive side of the x-axis (Fig. 3). Meanwhile, *SCARCITY_AWARE* has an ambiguous effect on *DPR_WILL_3* ($M_{SCARCITY_AWARE*CLIMATE}=0.03$ and $S_{SCARCITY_AWARE*CLIMATE}=0.08$).

To aid the result interpretation, we estimated the residents' probability of being willing to use recycled water directly based on the posterior coefficients of the model. Fig. 4 shows the illustration, where the y-axis represents the probability of being willing to use direct recycled water, and the x-axis represents the awareness level of water scarcity. The colored lines distinguish whether the people believe in climate change or not. As can be seen,




Fig. 4. Probability of being willing to use direct recycled water. Source: Generated by authors using the coefficients' mean values.

for people without the belief in climate change's impact on the water cycle, the probability of being willing to use direct recycled water is not affected by the awareness level of water scarcity. Meanwhile, the awareness level of water scarcity is positively associated with the probability of being willing to use it when the resident believes in climate change's impact.

3.2. Model 2

Model 2 was fitted using a similar setup to Model 1 (i.e., iterations, warmup period, Markov chains). The simulation took 205 seconds to be completed; its results are shown in Table 3. The PSIS-LOO test again shows all *k*-values are below 0.012 (Fig. A2). Such *k*-estimates suggest the model fits the data well.

Table 3. Model 2's estimated results.

Parameters	Mean	Standard deviation	n_eff	Rhat
<i>Constant</i>	0.60	0.25	4437	1
<i>SCARCITY_AWARE</i>	0.12	0.09	3970	1
<i>SCARCITY_AWARE*CLIMATE</i>	0.05	0.06	5015	1

Source: Generated by authors using the bayesvl R package.

We also visualized the trace plots to confirm the Markov chain's convergence. Fig. 5 illustrates the mixing of all coefficients' Markov chains around an equilibrium, representing a good convergence signal.




Fig. 5. Model 2's trace plots. Source: Generated by authors using the bayesvl R package.

The simulated results manifest the positive effects of *SCARCITY_AWARE* ($M_{SCARCITY_AWARE}=0.12$ and $S_{SCARCITY_AWARE}=0.09$) and *SCARCITY_AWARE*CLIMATE* ($M_{SCARCITY_AWARE*CLIMATE}=0.05$ and $S_{SCARCITY_AWARE*CLIMATE}=0.06$) on *IPR_WILL_3*. The coefficients' posterior distributions are visualized in Fig. 6, confirming the high reliability of the association between *SCARCITY_AWARE* and *IPR_WILL_3* as its posterior distribution is located entirely on the positive side of the x-axis. Meanwhile, the effect of *SCARCITY_AWARE*CLIMATE* on *IPR_WILL_3* is only moderately reliable because a small portion of its distribution is still situated on the negative side of the x-axis.




Fig. 6. Model 2's posterior distribution. Source: Generated by authors using the bayesvl R package.

Figure 7, visualized based on the estimated parameters of Model 2, illustrates the residents' probability of being willing to use recycled water indirectly. It shows that

the willingness to use indirect recycled water increases regarding the awareness of water scarcity. The effect of water scarcity awareness on indirect recycled water usage willingness is positively moderated by the belief in climate change's impact on the water cycle.




Fig. 7. Probability of being willing to use indirect recycled water. Source: Generated by authors using the coefficients' mean values.

4. Discussion

The current study employed BMF analytics to examine the effect of residents' awareness of water scarcity on the willingness to use direct and indirect recycled potable water and whether the belief in climate change moderated the relationship. Analyzing the dataset of 1831 residents in New Mexico, USA, we found that for direct recycled potable water, the awareness of water scarcity only has a positive impact on the usage willingness when the residents believe in climate change. Meanwhile, for indirect recycled potable water, water scarcity awareness has a positive impact on recycled water usage willingness, which is further amplified by the belief in climate change.

These results confirm our Mindsponge-based assumptions that the residents' water scarcity awareness (information stored in the mind) can influence their recycled water usage willingness (an outcome of the information process), but the effect is conditional on their status of belief in climate change (core value within the mindset). The person's belief in climate change will make them more likely to perceive the uncertainty of water supply in the future, adding more perceived risks/costs to the water scarcity crises. When water scarcity is perceived to threaten the well-being of the person in the future, they will be more likely to seek, absorb, and accept solution-related information that helps alleviate the crises. As a result, recycled water usage ideation is more likely to emerge in people's minds, making them more willing to use direct and indirect recycled water.

Climate change belief is a crucial factor that moderates the relationship between water scarcity awareness and the emergence of recycled water usage ideation (subsequently, the usage willingness). However, climate change denialism is an existing problem in the US, hindering the efforts to motivate people to adopt sustainable water usage practices. People advocating climate change denialism reject scientific evidence of climate change or deny the role of humans as the cause of this crisis [62, 63]. Denialism is so pervasive that it is even embedded in political activities. For example, Florida Governor Ron DeSantis recently rejected \$350 million in federal funds to tackle climate change [64]. If the climate change denialism issues are not appropriately addressed, they will negatively affect not only climate change but also the water crisis in the US. Besides climate change beliefs, other factors involving mindsets like trust, beliefs, core values, worldviews, etc., can possibly moderate the relationship between water scarcity awareness and the willingness to use recycled water. Therefore, exploring these moderators is a potential research direction for future research.

Practically, the current study's findings suggest that informing the public about the current water crises and climate change issues can help improve their recycled water usage willingness, facilitating the implementation of recycled water projects. Moreover, building an eco-surplus culture among residents is no less critical as it helps shift their perspectives to be more environment-centered [65]. Eco-surplus culture is defined as "a set of pro-environmental attitudes, values, beliefs, and behaviors that are shared by a group of people to reduce negative anthropogenic impacts on environments as well as conserve and restore nature" [66]. As a result of this culture, stakeholders' thinking, decision-making, and actions will be influenced to produce more positive values "to reduce negative anthropogenic impacts on environments as well as conserve and restore nature" [66]. Residents with an eco-surplus culture can even go beyond basic sustainability and actively participate in creating environmental surplus impacts, hence improving the effectiveness and sustainability of long-term water conservation and climate change alleviation efforts [67-69].

Deep leverage points are required to foster the transitions of residents' eco-deficit core values in the mindset to environmental-healing core values (or eco-surplus core values). One potential leverage point is restoring the connection between people's mental realms and the natural world [70, 71]. Such connections can be forged through many pathways: science, community knowledge systems, art, literature, games, and lived

experience [49, 65, 70, 72]. For example, climate fiction (cli-fi) and climate horror (cli-hor) are some literary genres that are expected to raise awareness of climate change and environmental degradation (including water stress) [73, 74]. However, the literature should be used prudently to restore the mental links between people and the world with other sentient beings rather than creating intensely negative emotions that could lead to counterproductive effects on environmental engagement and persuasion [72, 74]. As artificial intelligence (AI) is gradually embedded in humans' lives, and urban generations can be deemed as digital native generations, AI can be harnessed as a useful tool to mitigate climate and environmental apathy (including apathy towards water stress) [75].

The study has several limitations, so we report them here for transparency [76]. First, residents' willingness to use recycled water was self-reported, so it might not necessarily correspond with actual behaviors. Moreover, the sample size is bound in the city of Albuquerque, so it does not represent areas with different geographical and climate characteristics in the US. Future studies should be conducted to validate the effects of water scarcity awareness and climate change belief on recycled water usage willingness in other areas with different geographical and climate characteristics.

5. Conclusions

The present research utilized BMF analytics to investigate how residents' awareness of water scarcity influences their willingness to utilize both direct and indirect recycled potable water and whether their belief in climate change moderates this relationship. Analyzing data from 1831 residents in New Mexico, USA, we discovered that regarding direct recycled potable water, awareness of water scarcity due to climate change only positively affects usage willingness when residents believe in climate change. Conversely, concerning indirect recycled potable water, awareness of water scarcity positively influences willingness to use recycled water, with this effect being magnified by belief in climate change. In practical terms, our study's findings imply that educating the public about current water crises and climate change issues can enhance their willingness to use recycled water, thereby facilitating the implementation of recycled water projects. Furthermore, fostering an eco-surplus culture among residents is crucial, as it encourages them to adopt more environmentally-centered perspectives. Residents with an eco-surplus culture may even exceed basic sustainability practices and actively contribute to generating environmental surplus impacts, thereby enhancing the effectiveness and sustainability of long-term water conservation and climate change mitigation efforts.

APPENDICES




Fig. A1. Model 1's PSIS-LOO test.




Fig. A2. Model 2's PSIS-LOO test.

CRediT author statement

Minh-Hoang Nguyen: Conceptualisation, Validation, Writing, Reviewing and Editing, Administration; Duc Manh Doan, Hanh Kim Dong, Van Thi Nguyen, Hanh Hong Dao, Duy Duc Trinh, Nhai Thi Nguyen, Kim Nguyet Kieu, Nhung Quynh Thi Le, Ha Thu Thi Hoang, Van Ngoc Thi Dam, Dung Hoang Do, Thu Thi Vu, Tu That Ton, Nhi Yen Nguyen, Nhi Van Nguyen, Thu Tai Le, Hoa Tuan Pham, Binh Thi Khuat, Tung Thanh Nguyen, Anh Viet Thuy Nguyen, Vu Thien Tran, Son Kim Thi Nguyen, Tra Thanh Nguyen: Writing - Original draft preparation; Hang Thanh Pham, Linh Ha Nguyen, Hien Thanh Thi Vu: Data curation; Linh Thu Hoang, Dung Kim Nguyen, Chi Yen Nguyen, Chi Linh Nguyen, Minh Duc Vu, Lan Phuong Thi Le: Writing, Reviewing and Editing; Van-Cuong Do: Validation, Writing, Reviewing and Editing.

ACKNOWLEDGEMENTS

We would like to express our gratitude to the Vietnam Institute for Advanced Study in Mathematics (VIASM) and Hanoi University (HANU) for organising the *Conference on Innovations of Mathematics Teaching in Social Sciences*, which provides conditions for the completion of this study.

COMPETING INTERESTS

The authors declare that there is no conflict of interest regarding the publication of this article.

REFERENCES

- [1] United Nations Educational Scientific and Cultural Organization (2023), *UN World Water Development Report 2023: Partnerships and Cooperation for Water*, <https://unesdoc.unesco.org/ark:/48223/pf0000384655>, accessed 30 December 2023.
- [2] United Nations Educational Scientific and Cultural Organization (2016), *IHP-VIII: Water Security: Responses to Regional and Global Challenges (2014-2021)*, <https://unesdoc.unesco.org/ark:/48223/pf0000225103>, accessed 20 October 2022.
- [3] J. Liu, H. Yang, S.N. Gosling, et al. (2017), "Water scarcity assessments in the past, present, and future", *Earth's Future*, **5**(6), pp.545-559, DOI: 10.1002/2016EF000518.
- [4] P. Eckert, R. Lamberts, C. Wagner (2008), "The impact of climate change on drinking water supply by riverbank filtration", *Water Science and Technology: Water Supply*, **8**(3), pp.319-324, DOI: 10.2166/ws.2008.077.
- [5] B. Ma, C. Hu, J. Zhang, et al. (2022), "Impact of climate change on drinking water safety", *ACS ES&T Water*, **2**(2), pp.259-261, DOI: 10.1021/acsestwater.2c00004.
- [6] A.J. McMichael (2015), "Extreme weather events and infectious disease outbreaks", *Virulence*, **6**(6), pp.543-547, DOI: 10.4161/21505594.2014.975022.
- [7] G. Nichols, I. Lake, C. Heaviside (2018), "Climate change and water-related infectious diseases", *Atmosphere*, **9**(10), DOI: 10.3390/atmos9100385.
- [8] P.H. Gleick (2014), "Water, drought, climate change, and conflict in Syria", *Weather, Climate, and Society*, **6**(3), pp.331-340, DOI: 10.1175/WCAS-D-13-00059.1.
- [9] X. Fan, X. Zhang, A. Yu, et al. (2023), "Assessment of the impacts of climate change on water supply system pipe failures", *Scientific Reports*, **13**(1), DOI: 10.1038/s41598-023-33548-7.
- [10] D. Brookshire, H. Gupta, O.P. Matthews (2013), *Water Policy in New Mexico: Addressing The Challenge of an Uncertain Future*, Taylor & Francis, 304pp.
- [11] W.P. Miller, R.A. Butler, T. Piechota, et al. (2012), "Water management decisions using multiple hydrologic models within the San Juan river basin under changing climate conditions", *Journal of Water Resources Planning and Management*, **138**(5), pp.412-420, DOI: 10.1061/(ASCE)WR.1943-5452.000023.
- [12] I. James (2023), "Colorado River Basin ranks among the world's most water-stressed regions, analysis finds", <https://www.latimes.com/environment/story/2023-08-16/states-face-high-water-stress-along-colorado-river>, accessed 1 September 2023.
- [13] B. Bass, N. Goldenson, S. Rahimi, et al. (2023), "Aridification of Colorado River Basin's snowpack regions has driven water losses despite ameliorating effects of vegetation", *Water Resources Research*, **59**(7), DOI: 10.1029/2022WR033454.
- [14] V. Gewin (2022), "New Mexico farmers face a choice: Pray for rain or get paid not to plant", <https://civileats.com/2022/11/08/new-mexico-farmers-face-a-choice-pray-for-rain-or-get-paid-not-to-plant/>, accessed 1 March 2023.
- [15] T. Wallace, N. Popovich (2022), "A 'perfect recipe for extreme wildfire': New Mexico's record-breaking, early fire season", *The New York Times*, <https://www.nytimes.com/interactive/2022/06/01/climate/new-mexico-wildfires.html>, accessed 20 June 2022.
- [16] Z. Karimidastanaei, T. Avellán, M. Sadegh, et al. (2022), "Unconventional water resources: Global opportunities and challenges", *Science of The Total Environment*, **827**, DOI: 10.1016/j.scitotenv.2022.154429.
- [17] A. Ahmed (2010), "An overview of conventional and non-conventional water resources in arid region: Assessment and constraints of the United Arab Emirates (UAE)", *Journal of Water Resource and Protection*, **2**(2), DOI: 10.4236/jwarp.2010.22020.
- [18] A.M. Negm (2019), *Conventional Water Resources and Agriculture in Egypt*, Springer, 706pp.
- [19] A.K. Vuppaladadiyam, N. Merayo, P. Prinsen, et al. (2019), "A review on greywater reuse: Quality, risks, barriers and global scenarios", *Reviews in Environmental Science Bio/Technology*, **18**, pp.77-99, DOI: 10.1007/s11157-018-9487-9.
- [20] K.J. Ormerod, C.A. Scott (2013), "Drinking wastewater: Public trust in potable reuse", *Science, Technology, and Human Values*, **38**(3), pp.351-373, DOI: 10.1177/016224391244473.

- [21] Y. Gao, Z. Li, K. Khan (2019), "Effect of cognitive variables and emotional variables on urban residents' recycled water reuse behavior", *Sustainability*, **11**(8), DOI: 10.3390/su11082208.
- [22] K.S. Fielding, S. Dolnicar, T. Schultz (2018), "Public acceptance of recycled water", *International Journal of Water Resources Development*, **35**(4), pp.551-586, DOI: 10.1080/07900627.2017.1419125.
- [23] C. Hou, Y. Wen, X. Liu, et al. (2021), "Impacts of regional water shortage information disclosure on public acceptance of recycled water - evidences from China's urban residents", *Journal of Cleaner Production*, **278**, DOI: 10.1016/j.jclepro.2020.123965.
- [24] W.H. Bruvold, P.C. Ward (1972), "Using reclaimed wastewater: Public opinion", *Journal (Water Pollution Control Federation)*, **44**(9), pp.1690-1696.
- [25] L.G. Cuerva, E.Z. Berglund, A.R. Binder (2016), "Public perceptions of water shortages, conservation behaviors, and support for water reuse in the US", *Resources, Conservation and Recycling*, **113**, pp.106-115, DOI: 10.1016/j.resconrec.2016.06.006.
- [26] Albuquerque Bernalillo County Water Utility Authority (2016), *Water 2120: Securing Our Water Future*, 309pp.
- [27] L.N. Distler (2018), *Potable Water Reuse in Albuquerque, NM: A Large Scale Community Survey to Understand Public Perceptions and The Impact of Educational Materials on Acceptance*, University of New Mexico, 126pp.
- [28] L.N. Distler, C.E. Scruggs (2020a), "Arid inland community survey on water knowledge, trust, and potable reuse. I: Description of findings", *Journal of Water Resources Planning and Management*, **146**(7), DOI: 10.1061/(ASCE)WR.1943-5452.0001218.
- [29] L.N. Distler, C.E. Scruggs, K.N. Rumsey (2020b), "Arid inland community survey on water knowledge, trust, and potable reuse. II: Predictive modeling", *Journal of Water Resources Planning and Management*, **146**(7), DOI: 10.1061/(ASCE)WR.1943-5452.0001219.
- [30] Q.H. Vuong, N.K. Napier (2015), "Acculturation and global mindsponge: An emerging market perspective", *International Journal of Intercultural Relations*, **49**, pp.354-367, DOI: 10.1016/j.ijintrel.2015.06.003.
- [31] Q.H. Vuong (2023), *Mindsponge Theory*, De Gruyter, 218pp.
- [32] I. Ajzen (1985), "From intentions to actions: A theory of planned behavior", *Action Control*, Springer Berlin Heidelberg, pp.11-39, DOI: 10.1007/978-3-642-69746-32.
- [33] I. Ajzen (1991), "The theory of planned behavior", *Organizational Behavior and Human Decision Processes*, **50**(2), pp.179-211.
- [34] K.E. Gibson, A.J. Lamm, K.M. Woosnam, et al. (2021), "Predicting intent to conserve freshwater resources using the theory of planned behavior (TPB)", *Water*, **13**(18), DOI: 10.3390/w13182581.
- [35] S.S. Ho, Y. Liao, S.J.E.C. Rosenthal (2015), "Applying the theory of planned behavior and media dependency theory: Predictors of public pro-environmental behavioral intentions in Singapore", *Environmental Communication*, **9**(1), pp.77-99, DOI: 10.1080/17524032.2014.932819.
- [36] A.P. Howell, B.R. Shaw, G. Alvarez (2015), "Bait shop owners as opinion leaders: A test of the theory of planned behavior to predict pro-environmental outreach behaviors and intentions", *Environment and Behavior*, **47**(10), pp.1107-1126, DOI: 10.1177/0013916514539684.
- [37] C.A. Klöckner (2013), "A comprehensive model of the psychology of environmental behaviour - A meta-analysis", *Global Environmental Change*, **23**(5), pp.1028-1038, DOI: 10.1016/j.gloenvcha.2013.05.014.
- [38] K.E. Gibson, A.J. Lamm, K.W. Lamm, et al. (2023), "Integrating the theory of planned behavior and motivation to explore residential water-saving behaviors", *Water*, **15**(17), DOI: 10.3390/w15173034.
- [39] Q.H. Vuong, M.H. Nguyen, V.P. La (2022), *The Mindsponge and BMF Analytics for Innovative Thinking in Social Sciences and Humanities*, De Gruyter, 430pp.
- [40] L.N. Distler, C.E. Scruggs (2020c), "Survey data on perceptions of water scarcity and potable reuse from water utility customers in Albuquerque, New Mexico", *Data in Brief*, **29**, DOI: 10.1016/j.dib.2020.105289.
- [41] M.H. Nguyen, V.P. La, T.T. Le, et al. (2022a), "Introduction to Bayesian mindsponge framework analytics: An innovative method for social and psychological research", *MethodsX*, **9**, DOI: 10.1016/j.mex.2022.101808.
- [42] O. Asamoah, J.A. Danquah, D. Bamwesigye, et al. (2023), "The perception of the locals on the impact of climate variability on non-timber forest products in Ghana", *Acta Ecologica Sinica*, DOI: 10.1016/j.chnaes.2023.07.004.
- [43] Q.V. Khuc, T. Dang, M. Tran, et al. (2023a), "Household-level strategies to tackle plastic waste pollution in a transitional country", *Urban Science*, **7**(1), DOI: 10.3390/urbansci7010020.
- [44] Q.V. Khuc, M.H. Nguyen, T.T. Le, et al. (2022), "Brain drain out of the blue: Pollution-induced migration in Vietnam", *International Journal of Environmental Research and Public Health*, **19**(6), DOI: 10.3390/ijerph19063645.
- [45] Q.V. Khuc, M. Tran, T. Nguyen, et al. (2023b), "Improving energy literacy to facilitate energy transition and nurture environmental culture in Vietnam", *Urban Science*, **7**(1), DOI: 10.3390/urbansci7010013.
- [46] P. Mantello, M.T. Ho, M.H. Nguyen, et al. (2023), "Machines that feel: Behavioral determinants of attitude towards affect recognition technology - upgrading technology acceptance theory with the mindsponge model", *Humanities and Social Sciences Communications*, **10**, DOI: 10.1057/s41599-023-01837-1.
- [47] M.H. Nguyen, T.T. Le, M.T. Ho, et al. (2021), "Alice in suicideland: Exploring the suicidal ideation mechanism through the sense of connectedness and help-seeking behaviors", *International Journal of Environmental Research and Public Health*, **18**(7), DOI: 10.3390/ijerph18073681.
- [48] M.H. Nguyen, T.T. Le, Q.H. Vuong (2023a), "Ecomindsponge: A novel perspective on human psychology and behavior in the ecosystem", *Urban Science*, **7**(1), DOI: 10.3390/urbansci7010031.

- [49] M.H. Nguyen, M.H.T. Nguyen, R. Jin, et al. (2023b), "Preventing the separation of urban humans from nature: The impact of pet and plant diversity on biodiversity loss belief", *Urban Science*, **7**(2), DOI: 10.3390/urbansci7020046.
- [50] Q.H. Vuong, T.T. Le, R. Jin, et al. (2023a), "Near-suicide phenomenon: An investigation into the psychology of patients with serious illnesses withdrawing from treatment", *International Journal of Environmental Research and Public Health*, **20**(6), DOI: 10.3390/ijerph20065173.
- [51] J.R. Cogle (2012), "What makes a quality therapy? A consideration of parsimony, ease, and efficiency", *Behavior Therapy*, **43**(3), pp.468-481.
- [52] H.A. Simon (2001), "Science seeks parsimony, not simplicity: Searching for pattern in phenomena", *Simplicity, Inference and Modelling: Keeping It Sophisticatedly Simple*, Cambridge University Press, pp.32-72.
- [53] J. Gill (2014), *Bayesian Methods: A Social and Behavioral Sciences Approach*, CRC Press, 752pp.
- [54] L.G. Halsey, D.C. Everett, S.L. Vowler, et al. (2015), "The fickle P value generates irreproducible results", *Nature Methods*, **12**(3), pp.179-185.
- [55] E.J. Wagenmakers, M. Marsman, T. Jamil, et al. (2018), "Bayesian inference for psychology. Part I: Theoretical advantages and practical ramifications", *Psychonomic Bulletin Review*, **25**(1), pp.35-57, DOI: 10.3758/s13423-017-1343-3.
- [56] A. Vehtari, J. Gabry (2019), "Bayesian stacking and pseudo-BMA weights using the loo package", <https://mc-stan.org/loo/articles/loo2-weights.html>, accessed 20 October 2022.
- [57] A. Vehtari, A. Gelman, J. Gabry (2017), "Practical Bayesian model evaluation using leave-one-out cross-validation and WAIC", *Statistics Computing*, **27**(5), pp.1413-1432, DOI: 10.1007/s11222-016-9696-4.
- [58] R. McElreath (2018), *Statistical Rethinking: A Bayesian Course with Examples in R and Stan (Chapman & Hall/CRC Texts in Statistical Science)*, 1st Edition, 487pp.
- [59] S.P. Brooks, A. Gelman (1998), "General methods for monitoring convergence of iterative simulations", *Journal of Computational and Graphical Statistics*, **7**(4), pp.434-455.
- [60] V.P. La, Q.H. Vuong (2019), "Bayesvl: Visually learning the graphical structure of Bayesian networks and performing MCMC with Stan", *The Comprehensive R Archive Network (CRAN)*, <https://cran.r-project.org/web/packages/bayesvl/index.html>, accessed 1 October 2022.
- [61] Q.H. Vuong (2018), "The (ir)rational consideration of the cost of science in transition economies", *Nature Human Behaviour*, **2**(1), DOI: 10.1038/s41562-017-0281-4.
- [62] S. Goldenberg (2010), "US Senate's top climate sceptic accused of waging 'McCarthyite witch-hunt'", *The Guardian*, <https://www.theguardian.com/environment/2010/mar/01/inhofe-climate-mccarthyite>, accessed 20 October 2022.
- [63] G. Readfearn (2015), "Doubt over climate science is a product with an industry behind it", *The Guardian*, <https://www.theguardian.com/environment/planet-oz/2015/mar/05/doubt-over-climate-science-is-a-product-with-an-industry-behind-it>, accessed 22 October 2022.
- [64] T. Otten (2023), "DeSantis rejected \$350 million in climate funding before Hurricane Idalia", *The New Republic*, <https://newrepublic.com/post/175301/desantis-rejected-350-million-climate-funding-florida-hurricane-idalia>, accessed 2 September 2023.
- [65] Q.H. Vuong (2021), "The semiconducting principle of monetary and environmental values exchange", *Economics and Business Letters*, **10**(3), pp.284-290, DOI: 10.17811/ebl.10.3.2021.284-290.
- [66] M.H. Nguyen, T.E. Jones (2022b), "Building eco-surplus culture among urban residents as a novel strategy to improve finance for conservation in protected areas", *Humanities & Social Sciences Communications*, **9**, DOI: 10.1057/s41599-022-01441-9.
- [67] M.H. Nguyen, M.P.T. Duong, M.C. Nguyen, et al. (2023c), "Promoting stakeholders' support for marine protection policies: Insights from a 42-country dataset", *Sustainability*, **15**(16), DOI: 10.3390/su151612226.
- [68] M.H. Nguyen, T.E. Jones (2022c), "Predictors of support for biodiversity loss countermeasures and bushmeat consumption among Vietnamese urban residents", *Conservation Science and Practice*, **4**(12), DOI: 10.1111/csp2.12822.
- [69] A.K. Pradhananga, M.A. Davenport (2019), "Predicting farmer adoption of water conservation practices using a norm-based moral obligation model", *Environmental Management*, **64**(4), pp.483-496, DOI: 10.1007/s00267-019-01186-3.
- [70] D.J. Abson, J. Fischer, J. Leventon, et al. (2017), "Leverage points for sustainability transformation", *AMBIO*, **46**, pp.30-39, DOI: 10.1007/s13280-016-0800-y.
- [71] E. Kellner (2023), "Identifying leverage points for shifting water-energy-food nexus cases towards sustainability through the networks of action situations approach combined with systems thinking", *Sustainability Science*, **18**(1), pp.135-152, DOI: 10.1007/s11625-022-01170-7.
- [72] Q.H. Vuong, M.H. Nguyen (2023b), "Kingfisher: Contemplating the connection between nature and humans through science, art, literature, and lived experiences", *Pacific Conservation Biology*, DOI: 10.1071/PC23044.
- [73] N. Booth (2019), "For some horror writers, nothing is scarier than a changing planet", *The New York Times*, <https://www.nytimes.com/2019/10/19/books/review/eco-horror-annihilation-jeff-vandermeer-chernobyl.html>, accessed 1 October 2022.
- [74] M.S. Mayerson (2018), "The influence of climate fiction: An empirical survey of readers". *Environmental Humanities*, **10**(2), pp.473-500, DOI: 10.1215/22011919-7156848.
- [75] Q.H. Vuong, M.T. Ho (2024), "Escape climate apathy by harnessing the power of generative AI", *AI & Society*, DOI: 10.1007/s00146-023-01830-x.
- [76] Q.H. Vuong (2020), "The limitations of retraction notices and the heroic acts of authors who correct the scholarly record: An analysis of retractions of papers published from 1975 to 2019", *Learned Publishing*, **33**(2), pp.119-130, DOI: 10.1002/leap.1282.